Homework 2 Solution

We are using ADD instruction, so operands are signed numbers. As we are adding two negative numbers and result is also negative (sign bit not changed), this means **no overflow** occurred.

As we are adding two negative numbers and result is positive (sign bit changed), this means **overflow** occurred.

```
2. \$s0 = (0000\_0030)_{16} = (0000\_0000\_0000\_0000\_0000\_0000\_0011\_0000)_2

\$s1 = (0000\_0005)_{16} = (0000\_0000\_0000\_0000\_0000\_0000\_0101)_2
```

We will ignore the 16 least significant 0 bits in \$s1, and later shift the product accordingly.

Adding 30 0s at the left gives us the result:

3. $\$s0 = (0000_0008)_{16} = (0000_0000_0000_0000_0000_0000_1000)_2$ $\$s1 = (0000_0005)_{16} = (0000_0000_0000_0000_0000_0000_0101)_2$

 $X9 = Quotient = (0000_0001)_{16}$

4.

MOV X10, #0 #reset count to zero

Loop:

ANDI X11, X9, 1 #check if LSB is 1

ADD X10, X10, X11 #add LSB to count, so count is increased when LSB 1

LSR X9, X9, #1 #shift number to right by 1, thus next digit becomes new LSB CMP X9, #0

BGT Loop #loop until given number becomes zero

5. Computes the volume of a cylinder.

Pseudocode:

X9 = height X10 = radius X11 = 3.14 X11 = 3.14 * X10 * X10 * X9 $//volume = pi * radius^2 * height$